BRUHATH BENGALURU MAHANAGARA PALIKE

Yelahanka Division, Yelahanka Zone

Executive Engineeer
Yelahanka Division
B.B.M.P. Bengaluru - 64

APPROVED SCHEDULE –'B'

Name of Work:- Improvements to Roads and Drains at Yelahanka Old Town SC/ST area and AD colony and surrounding areas in Ward No. 02 of Yelahanka Sub division

Sl	Description	Unit	Approved Qty	Approved Rate Technical Manager (West) KRIDL, BBMP,	
				Rate	Rate in Words
1	KSRRB 300 - Excavation for road, drains and similar works KSRRB 300-1. Earthwork excavation by manual means in ordinary soil involving an average horizontal throw upto 2 meters and an average lift upto 0.5 m, excavated surface leveled and sides neatly dressed, the disposed earth to be leveled neatly after breaking of clods complete as per specifications. MORTH / Chapter 3 (P.No-143, I.No-19.1)	Cum	1048.50	215.28	Rupees Two Hundred Fifteen And Paise Twenty Eight Only
2	KSRRB M2100-10. Providing and laying Plain cement concrete of mix 1:3:6 with OPC @ 220kgs, with crushed 40mm and down size graded granite metal coarse aggregates @0.89cum and fine aggregates @ 0.46cum, in foundation mechanically mixed, placed in foundation and compacted by vibration including curing for 14 days including cost of all materials, labour, HOM curing, form works, scaffolding and centering complete as per specifications. (P.No-222.I No-27.18)	Cum	238.05	5421.90	Rupees Five Thousand Four Hundred Twenty One And Paise Ninety Only
3	Providing and laying plain/reinforced cement concrete for side drains using M20 nominal mix concrete with OPC at 300 kgs. With 20mm and sown size granite metal course aggregates at 0.69 cum and fine aggregates at 0.43 cum machine mixed, well compcted for walls and bottom including centring shuttering cost of material HOM of machinary curing etc., complete execluding cost of steel as per MORTH specification no. 1500, 1700, 2200 including cost of material labour HOM complete as per specification. (P.No.271, I.No.37.59.2 of PW. P&IWTD S.R 2018-19)	Cum	222.15	7070.20	Rupees Seven Thousand Seventy And Paise Twenty Only

EXECUTIVE ENGINEER-4
KRIDL BBMP DIVISION
BENGALURU-560 010

	Description	Unit	Approved Qty	Approved Rate Technical Manager (West) KRIDL, BBMP,	
				Rate	Rate In Words
	KSRRB - M2300-14: Providing TMT steel reinforcement for R.C.C work including straightening, cutting, bending, hooking, palcing in position, lapping and / or welding wherever required, tying with binding wire and anchoring to the adjoining memebrs wherever necessary complete as per design (laps, hooks and wastage shall not be measured and paid) cost of materials, labour, HOM of machinery complete as per specifications.MORTH Specification No. 1600 & 2200 for TMT bars Fe 500. (P.No.239, I.No.29.29.2 of PW, P&IWTD S.R 2018-19)	Tonne	15.78	73992.24	Rupees Seventy Three Thousand Nine Hundred Ninety Two And Paise Twenty Four Only
5	Providing and fixing RCC precast cover slab of 100mm thick for drain in cement concrete 1:1.5:3 using graded granite jelly 20mm and down size with steel reinforcement, including form work, lift charges, curing and concrete finished surfaces on both sides etc, complete and as per drawing and the directions of Engineer in-charge. (Data Rate)	Sqm	506.25	2337.00	Rupees Two Thousand Three Hundred Thirty Seven Only
6	Providing and fixing RCC precast cover slab of 250mm thick made out of CC 1:2:4 and jelly 20mm and down size with steel reinforcement, including form work, lift charges, curing and concrete finished surfaces on both sides etc, complete and as per drawing and the directions of Engineer in-charge. (Data Rate)	Sqm	18.00	5418.00	Rupees Five Thousand Four Hundred Eighteen Only

EXECUTIVE ENGINEER-4
KRIDL BBMP DIVISION
BENGALURU-560 010

	Description	Unit	Approved Qty	Approved Rate Technical Manager (West) KRIDL, BBMP,	
				Rate	Rate in Words
	Constructing un-reinforced, plain cement concrete for pavements using Grade concrete M30 with OPC at 360 kg/cum and coarse aggregate 0.69cum, fine aggregate 0.46cum. over a prepared base with OPC coarse aggregate at 0.69 cum, fine aggregates at 0.46 cum,Coarse and fine aggregate conforming to IS:383-2016, with Superplastizer at 3 lts conforming to IS 9103-2008. mixed in a concrete mixer of not less than 0.6 cum capacity and appropriate weigh batcher as per approved mix design, laid in approved fixed side form work (steel channel, laying and fixing of 125 micron thick polythene film, wedges, steel plates including levelling the form work as per drawing). & Spreading the concrete with shovels, rackers compacted using needle, screed and plate vibrator and finished with floaters in a continuous operation including provision of contraction, expansion, construction and longitudinal joints,including groove cutting charges, joint filler, separation membrane of impermiable plastic sheet of 125 micron, sealant primer, joint sealant, admixtures as approved, curing compound, finishing to lines and grades, textured with texturing machine	Cum	130.28	5210.96	Rupees Five Thousand Two Hundred Ten And Paise Ninety Six Only
8	Vaccum De- writing with vaccum pump and suction mat and compaction with skin flater clubbed with floatiog disc including cost of generator, HOM of machinery Sereed Vibratory Power Floaterblade and diisc etc. with all lead and lift. (Page No 176 Item No 22.7)	Sqm	868.50	72.08	Rupees Seventy Two And Paise Eight Only
9	KSRB 2-2.1 : Earthwork excavation for foundation of buildings, water supply, sanitary lines and electrical conduits either in pits or in trenches 1.5m and above in width, in ordinary soil not exceeding 1.5 m. in depth including dressing the bottom and sides of pits and trenches, stacking the excavated soil clear from edges of excavation with lead upto 50 m. after breaking of clods complete as per specifications. specification. No. KBS 2.1(a) / 2.3.5 (KPWD SR 2016-17, Page No.5, Item No.2.3)	Cum	35.32	204.12	Rupees Two Hundred Four And Paise Twelve Only

EXECUTIVE ENGINEER-4
KRIDL BBMP DIVISION
BENGALURU-560 010

	Description	Unit	Approved Qty	Approved Rate Technical Manager (West) KRIDL, BBMP,	
				Rate	Rate in Words
	KSRB 2-2.4 : Excavation 1.5m and above in width in soft rock without blasting for foundation of buildings, water supply, sanitary lines and electrical conduits either in pits or in trenches not exceeding 1.5 m. in depth, stacking the excavated stuff from edges of excavation with lead upto 50m including cost of explosives, labour and HOM of equipment complete as per specifications. specification. No. KBS 2.1.C / 2.9.4 / 2.18 / 2.19 (KPWD SR 2016-17, Page No.5, Item No.2.6)	Cum	15.14	953.64	Rupees Nine Hundred Fifty Three And Paise Sixty Four Only
11	KSRB 2-4 : Refilling available earth around pipe lines, cables in layers not exceeding 20cms in depth, compacting each deposited layer by ramming after watering with lead upto 50m. and lift upto 1.5 m. including cost of all labour complete as per specifications. (KPWD SR 2016-17, Page No.6, Item No.2.11)	Cum	50.45	82.08	Rupees Eighty Two And Paise Eight Only
12	KSRB 4-1.2 : Providing and laying in position plain cement concrete of mix 1:3:6 with OPC cement @ 220kgs, with 40mm and down size graded granite metal coarse aggregates @0.892Cum and fine aggregates @ 0.465Cum machine mixed, machine mixed, concrete laid in layers not exceeding 15 cms. thick, well compacted, in foundation including cost of all materials, labour, HOM of machinery, curing complete as per specifications.Specification No. KBS 4.1,4.2 (KPWD SR 2016-17, Page No.12, Item No.4.2)	Cum	13.80	5449.68	Rupees Five Thousand Four Hundred Forty Nine And Paise Sixty Eight Only

EXECUTIVE ENGINEER-4
KRIDL BBMP DIVISION
BENGALURU-560 010

	Description	Unit	Approved Qty	Approved Rate Technical Manager (West) KRIDL, BBMP,	
				Rate	Rate in Words
	KSRB 4.2.1 : Providing and laying in position reinforced cement concrete of Design mix M25 with OPC cement @ 340kgs, with 20mm and down size graded granite metal coarse aggregates @0.70 cum and fine aggregtes @ 0.47cum, with super plasticisers @ 3 liters confirming to is 9103-1999 reafirmed-2008 at machine mixed, concrete laid in layers not exceeding 15 cms thick, vibrated for all works in foundation for footings, pedastals, retaining walls, return walls, walls (any thickness) including attached pilasters, columnspillars, posts, struts, buttresses, bed blocks, anchor blocks & plinths etc., including cost of all materials, labour, HOM of machinery, curing, complete but excluding cost of reinforcement as per specifications. Specification No. KBS 4.1, 4.6 (Page No. 13, It No. 4.10 of KPWD S.R 2016-17)	Cum	6.55	6718.68	Rupees Six Thousand Seven Hundred Eighteen And Paise Sixty Eight Only
14	KSRB 4.2.2 : Providing and laying in position reinforced cement concrete of Design mix M20 with OPC cement @ 320kgs, with 20mm and down size graded granite metal coarse aggregates @0.69cum and fine aggregtes @ 0.460 cum, with super plasticisers @ 3 liters confirming to is 9103-1999 reafirmed-2008, machine mixed, concrete laid in layers not exceeding 15 cms thick, vibrated for all works in foundation for footings, pedastals, retaining walls, return walls, walls (any thickness) including attached pilasters, columnspillars, posts, struts, buttresses, bed blocks, anchor blocks & plinths etc., including cost of all materials, labour, HOM of machinery, curing, complete but excluding cost of reinforcement as per specifications. Specification No. KBS 4.1, 4.6 (Page No. 13, It No. 4.11 of KPWD S.R 2016-17)	Cum	25.14	6491.88	Rupees Six Thousand Four Hundred Ninety One And Paise Eighty Eight Only

EXECUTIVE ENGINEER-4
KRIDL BBMP DIVISION
BENGALURU-560 010

	Description	Unit	Approved Qty	Approved Rate Technical Manager (West) KRIDL, BBMP,	
				Rate	Rate in Words
	KSRB 4.9.2 : Providing T.M.T steel reinforcement for R.C.C work including straightening, cutting, bending, hooking, placing in position, lapping and / or welding wherever required, tying with binding wire and anchoring to the adjoining members wherever necessary complete as per design (laps, hooks and wastage shall not be measured and paid) cost of materials, labour, HOM of machinery complete as per specifications and as per directions of the Engineer-in-charge. Specification No. KBS 4.6.3(Item no: 4.46.2, Page no: 17 of KPWD S.R 2016-17).	Tonne	3.63	65455.56	Rupees Sixty Five Thousand Four Hundred Fifty Five And Paise Fifty Six Only
16	KSRB 4-6.1 : Providing and removing centering, shuttering, strutting, propping etc., and removal of form work for foundations, footings, bases of columns for mass concrete including cost of all materials, labour complete as per specificaitons. Specification No. KBS 4.6.2 (Page No. 15, It No. 4.28 of KPWD S.R 2016-17)	Sqm	25.20	249.48	Rupees Two Hundred Forty Nine And Paise Forty Eight Only
17	KSRB 4-6.5 : Providing and removing centering, shuttering, strutting, propping etc., for columns, pillars, post and struts, square / rectangular/ polygon in plan including cost of all materials, labour complete as per specifications. Specification No. KBS 4.6.2 (Page No. 16, It No. 4.32 of KPWD S.R 2016-17)	Sqm	46.89	395.28	Rupees Three Hundred Ninety Five And Paise Twenty Eight Only
18	KSRB 4-6.7 :Providing and removing centering, shuttering, strutting, propping etc., and removal of form work for sides and soffits of beams, beam haunchings, cantilever girders, bressumers and lintels not exceeding 1m in depth including cost of all materials, labour complete as per specifications. Specification No. KBS 4.6.2 (Page No. 16, It No. 4.34 of KPWD S.R 2016-17)	Sqm	80.16	276.48	Rupees Two Hundred Seventy Six And Paise Forty Eight Only
19	KSRB 4-6.9 :Providing and removing centering, shuttering, strutting, propping etc., for edges of slabs and breaks in floor including cost of all materials, labour complete as per specifications. Specification No. KBS 4.6.2 (Page No. 16, It No. 4.36 of KPWD S.R 2016-17)	Sqm	5.70	732.24	Rupees Seven Hundred Thirty Two And Paise Twenty Four Only

EXECUTIVE ENGINEER-4
KRIDL BBMP DIVISION
BENGALURU-560 010

	Description	Unit	Approved Qty	Approved Rate Technical Manager (West) KRIDL, BBMP,	
				Rate	Rate In Words
	KSRB 4-6.3 : Providing and removing centering, shuttering, strutting, propping etc., and removal of form work for flat surface such as suspended floors, roofs, landings, balconies and likes, thickness above 200 mm including cost of all materials, labour complete as per Specification. Specification No. KBS 4.6.2 (Page No. 15, It No. 4.30 of KPWD S.R 2016-17)	Sqm	79.49	255.96	Rupees Two Hundred Fifty Five And Paise Ninety Six Only
21	KSRB 5.2-3 : Providing and constructing granite / trap / basalt size stone masonry in foundation with cement mortar 1:6, stone hammerd dressed in courses not less than 20 cms high, bond stones at two m. apart in each course including cost of materials, labour, curing complete as per specifications. KBS 5.1.13 (KPWD SR 2016-17, Page No.23, Item No.5.6)	Cum	39.04	4521.96	Rupees Four Thousand Five Hundred Twenty One And Paise Ninety Six Only
22	KSRB 6-1.1 :Providing and constructing burnt brick masonry with approved quality of non-modular bricks of standard size of class designation 3.5 Newton per sqmm with mud mortar for basement and superstructure including cost of materials, labour charges, scaffolding, curing complete as per specifications Specification No. KBS 6.2. (KPWD SR 2016-17, Page No.27, Item No.6.1)	Cum	19.93	5523.12	Rupees Five Thousand Five Hundred Twenty Three And Paise Twelve Only
23	KSRB15-3.7 : Providing 18mm thick cement plaster in single coat with cement mortar 1:3, to brick masonry including rounding off corners wherever required smooth rendering, : Providing and removing scaffolding, including cost of materials, labour, curing complete as per specifications. (Page No. 113, It No. 15.15 of KPWD S.R 2016-17)	Sqm	98.28	263.52	Rupees Two Hundred Sixty Three And Paise Fifty Two Only
24	KSRB15-3-13 : Providing 12mm thick cement plaster in single coat with cement mortar 1:3, to ceiling including rounding off corners wherever required smooth rendering, : Providing and removing scaffolding, including cost of materials, labour, curing complete as per specifications. (Page No. 114, It No. 15.21 of KPWD S.R 2016-17)	Sqm	50.71	208.44	Rupees Two Hundred Eight And Paise Forty Four Only

EXECUTIVE ENGINEER-4
KRIDL BBMP DIVISION
BENGALURU-560 010

	Description	Unit	Approved Qty	Approved Rate Technical Manager (West) KRIDL, BBMP,	
				Rate	Rate in Words
	KSRB15-3.4 : Providing 15mm thick cement plaster in single coat with cement mortar 1:3, to brick masonry including rounding off corners wherever required smooth rendering, : Providing and removing scaffolding, including cost of materials, labour, curing complete as per specifications. (Page No. 113, It No. 15.12 of KPWD S.R 2016-17)	Sqm	90.92	221.40	Rupees Two Hundred Twenty One And Paise Forty Only
26	KSRB 15-15.1 : Providing and applying painting in two coats with plastic emulsion paint of approved brand on wall surface to give an even approved shade after thoroughly brushing the surface, free from mortar drops and other foreign matter including preparing the surface even and sand paper smooth, cost of materials, labour, complete as per specifications. (Page No. 117, It No. 15.51.1 of KPWD S.R 2016-17)	Sqm	239.90	76.68	Rupees Seventy Six And Paise Sixty Eight Only
27	KSRB 7.9 : Providing and fixing M.S.grill work for windows and ventilators weighing 21kg/sqm using M.S. flats, or M.S. square rods, or combination of M.S. flats and square rods as per approved design, drawing including cutting steel sections and welding the same to required pattern with a coat of red lead primer, cost of materials, fixtures, labour and HOM of machinery complete as per specifications. Specification No. KBS 7.12. (Page No. 32, It No. 7.9 of KPWD S.R 2016-17)	Kgs	158.76	84.24	Rupees Eighty Four And Paise Twenty Four Only
28	KSRB 9.4-1 : Providing Teak wood frames of doors, windows, clerestory windows, ventilators and other frames, wrought, framed or assembled including making plaster groves (excluding cost of cement concrete and side clamps), but including cost of materials, labour, HOM of machineries complete as per specifications. Specification No. KBS 9.33. (Page No. 51, It No. 9.10 of KPWD S.R 2016-17)	Cum	0.07	########	Rupees Two Lakh(s) Seven Hundred Eighty Seven And Paise Twelve Only
29	KSRB 9.5-1 : Providing and fixing in position fully panelled Teak wood shutters for doors, styles and rails of 40mm. thick with bottom and lock rails 180mm wide top rail and styles 100mm wide as per drawing and panels of 25mm thick including cost of materials, labour, HOM of machineries complete as per specifications. (excluding cost of fixtures) Specification No. KBS 9.34 (Page No.51, It No. 9.14 of KPWD S.R 2016-17)	Sqm	2.52	8964.00	Rupees Eight Thousand Nine Hundred Sixty Four Only

EXECUTIVE ENGINEER-4
KRIDL, BBMP DIVISION

	Description	Unit	Approved Qty	Approved Rate Technical Manager (West) KRIDL, BBMP,	
				Rate	Rate In Words
	Providing and fixing aluminium fixtures like aldrops of size 300 X 16mm towe bolts of size 200 X 12 mm, Latches of size 250 X 12 mm, 100mm length oxidized iron hinges, handles of size 150mm, door stopper and door brush of approved make and quality including cost and conveyance of all materials and as per the direction of EIC of work with all lead and lift and as directed by the engineer incharge of work, Single shutter.	Sqm	3.00	4691.52	Rupees Four Thousand Six Hundred Ninety One And Paise Fifty Two Only
31	KSRB 15-17.6 : Providing and applying painting two coats (excluding priming coat) on new wood surface and / or wood based surface with enamel paint to give an even shade, cleaning the surface of all dirt, dust and foreign matter, sand papering including cost of materials, labour, complete as per specifications. (Page No.119, It No. 15.60.1 of KPWD S.R 2016-17)	Sqm	5.04	90.72	Rupees Ninety And Paise Seventy Two Only
32	KSRB 15-17.8 : Extra over Item No. 15-17.6 for applying every subsequent coat of enamel paint to give an even shade after cleaning the surface of all dirt, dust and foreign matter, sand papering including cost of materials, labour, complete as per specifications. (Page No.119, It No. 15.60.2 of KPWD S.R 2016-17)	Sqm	5.04	51.84	Rupees Fifty One And Paise Eighty Four Only
33	Providing and fixing 20mm thick gang saw water cut LAKARED granite in CM 1:4 proportion with a coat of rough plastering using CM 1:4, cut to required shape, pattern with paper joints, finished with cement mortar using white cement and colour pigments to match the colour of slab making through jointing with sealant, grooves in joints including cost of curing etc., complete including cost and conveyance of all materials, labour for all items of work, HOM of equipment etc., complete as per specification . (P.No. 109, I.No. 14.60 of PWD SR 2016-17)	Sqm	50.71	3990.60	Rupees Three Thousand Nine Hundred Ninety And Paise Sixty Only

EXECUTIVE ENGINEER-4
KRIDL BBMP DIVISION
BENGALURU-560 010

	Description	Unit	Approved Qty	Approved Rate Technical Manager (West) KRIDL, BBMP,	
				Rate	Rate in Words
	Providing and fixing of wall cladding using 20 mm thick gang saw water cut granite in CM 1:3 proportion cut to required shape patron with paper joint finished with cement mortar using white cement and colour pigments to match the colour of slab making through jointing with sealant, making holes 25mm × 12mm grooves in joints including curing etc., complete - with grey granite 20mm thick gang saw with minimum width 1200.(Page No.110, It No. 14.67.1 of KPWD S.R 2016-17	Sqm	66.14	2478.60	Rupees Two Thousand Four Hundred Seventy Eight And Paise Sixty Only
35	KSRB 10-3 : Providing and laying integral cement based waterproofing treatment including preparation of surface as required for treatment of roofs, balconies, terraces etc., consisting of following application. (a) Applying and grouting a slurry coat of neat cement using 2.75 kg/sqm of cement admixed with proprietary water proofing compound conforming to IS:2645 over the RCC slab after cleaning the surface before treatment. (b) Laying cement concrete using broken brick bats 25mm to 100mm size with 50% of cement mortar 1:5 admixed with proprietary water proofing compound conforming IS:2645 over 20mm thick layer of cement mortar 1:5 admixed with proprietary water proofing compound to required slope and treating similarly the adjoining walls upto 300mm height including rounding off junctions of walls and slabs. (c) After two days of proper curing, applying a second coat of cement lurry admixed with proprietary water proofing compound (d) Finishing the surface with 20mm thick jointless cement mortar of mix 1:4 admixed with proprietary water proofing compound and finally finishing the surface with trowel and neat cement slurry and making of 300x300mm	m	57.14	976.32	Rupees Nine Hundred Seventy Six And Paise Thirty Two Only
36	Supplying heavy gauge PVC conduit pipe..... dia confirming to IS 2509 with suitable size benda, junction boxes, adhesive paste etc., and fixing using inverted wood plugs in case of RCC ceiling and RCC wall stone structure or rawl plugs in case of brick walls and cement plastering damaged portion using heavy gauge saddles at an interval of 700mm using NF screws. (ELE SR 2014-15Page-2, Item-1.1.2)	m	25.00	70.00	Rupees Seventy Only

EXECUTIVE ENGINEER-4
KRIDL BBMP DIVISION

	Description	Unit	Approved Qty	Approved Rate Technical Manager (West) KRIDL, BBMP,	
				Rate	Rate In Words
	Supplying..... mm dia 2mm/2.5mm thick heavy gauge PVC conduit pipe with suitable size bends, metal/PVC junction boxes adhesive paste etc., and running before concreting the slab. The conduit should be tied to the reinforcement rods by using binding wires and unused ways of junction boxes and pipe ends should be covered using PVC end enclosures. run with 18SWG GI fish wire wherever necessary. (ELE SR 2014-15 Page-2, Item-1.2.2)	m	25.00	57.00	Rupees Fifty Seven Only
38	Groove cutting in the wall supplying.....dia 2mm/2.5mm thick heavy gauge PVC Conduit Pipe with bends, metal junction boxes adhesive paste etc., and bracing U or J hooks and cement plastering up to the surface of the brick level and run with 18 SWG GI fish wire run through out conduit wherever necessary. (ELE SR 2014-15 Page-2, Item-1.3.2)	m	30.00	58.00	Rupees Fifty Eight Only
39	Supplying and fixing sheet metal box made out of 18 SWG sheet metal with necessary holes for cable/conduit entry as required with one coat of approved make etc.(ELE SR 2010-11 Page-2, Item-1.4)	each			Rupees Nil
	c) 135x75x65mm		5.00	102.00	Rupees One Hundred Two Only
	d)180x90x65mm		5.00	110.00	Rupees One Hundred Ten Only
	e)200x90x65mm		5.00	120.00	Rupees One Hundred Twenty Only
40	Supplying and fixing PVC/metal conduit accessories.(3/5) (ELE SR 2014-15 Page-3, Item-1.5.3)	each			Rupees Nil
	d)40mm junction box		5.00	53.00	Rupees Fifty Three Only
	c) 32mm deep junction box		5.00	65.00	Rupees Sixty Five Only
41	Supplying and flush mounting teak wooden box without front plank, made of not less than 12mm thick wood, after due groove cutting, necessary masonry patch work cpmplete.(ELE SR 2014-15 Page-3, Item-6)	m			Rupees Nil
	a)12xx"12"x3" (330x300x76mm		5.00	116.00	Rupees One Hundred Sixteen Only
	b)12"x9"x3" (300x228x76)		5.00	98.00	Rupees Ninety Eight Only

	Description	Unit	Approved Qty	Approved Rate Technical Manager (West) KRIDL, BBMP,	
				Rate	Rate in Words
	Supplying and wiring adopting loop system in existing PVC Conduit / casing capping using copper PVC insulated multi strand 2x1.5Sqmm copper wire with a 6Amps flush type SP control switch shall be fixed on the existing plastic sheet/gang box, the other end of the wires shall be terminated with sufficient loose length in a wood/PVC round block. compelete for each outlet. (ELE SR 2014-15 Page-3, Item-8)	each			Rupees Nil
	a) Short point up to 3Mtr from tapping point to out let via switchEach point		5.00	174.00	Rupees One Hundred Seventy Four Only
	b) Medium point above 3Mtr up to 6Mtr from tapping point to out let via switch (Each point)		5.00	245.00	Rupees Two Hundred Forty Five Only
43	Supplying and wiring adopting loop system in existing PVC Conduit / casing capping using copper PVC insulated multi strand 2x1.5Sqmm copper wire without switch, the other end of the wires shall be terminated with sufficient loose length in a wood/PVC round block. complete for each outlet. (ELE SR 2014-15 Page-4, Item-9)	each			Rupees Nil
	a) Short point up to 3Mtr from tapping point to out let via switch box		5.00	144.00	Rupees One Hundred Forty Four Only
	b) Medium point above 3Mtr up to 6Mtr from tapping point to out let via switch box		5.00	215.00	Rupees Two Hundred Fifteen Only
44	Supplying and fixing superior quality modular switch mounting polycarbonate plate with necessary supporting back plate with required nos. of machine screws, bolts nuts etc., complete on the existing metal/PVC box. (ELE SR 2014-15 Page-16, Item-3.6.3)	each	10.00	173.00	Rupees One Hundred Seventy Three Only
45	Supplying and fixing of modular switch/ Socket/stepped electronic fan regulator/dimmer/telephone socket etc on existing modular switch plate..(ELE SR 2014-15 Page-16, Item-3.7)	each			Rupees Nil
	a) 6Amps one way.		10.00	63.00	Rupees Sixty Three Only
	i) 32Amps DP switch		10.00	164.00	Rupees One Hundred Sixty Four Only
	j) 6/16Amps universal socket		5.00	147.00	Rupees One Hundred Forty Seven Only

EXECUTIVE ENGINEER-4
KRIDL BBMP DIVISION
BENGALURU-560 010

	Description	Unit	Approved Qty	Approved Rate Technical Manager (West) KRIDL, BBMP,	
				Rate	Rate in Words
	Supplying and fixing 32Amps security and energy saving DP switch with key tag suitable to operate on 230 Volts, 50Hz AC supply &completely wired on existing box. (ELE SR 2014-15 Page-17, Item-3.8)	each	10.00	168.00	Rupees One Hundred Sixty Eight Only
47	Wiring for lighting/power circuit using one of PVC insulated 1100v grade, multistrand Copper conductor single core cable in open or concealed system of wiring. (ELE SR 2014-15 Page-6, Item-2.5)	m			Rupees Nil
	a. 1 sqmm.		25.00	13.00	Rupees Thirteen Only
	b. 1.5 sqmm		25.00	18.60	Rupees Eighteen And Paise Sixty Only
	C.6 sqmm		25.00	56.80	Rupees Fifty Six And Paise Eighty Only
48	Supplying and fixing of PVC casing and capping on the wall or ceilng using necessary materials like bends, screws at an interval of 300mm .... Etc as required. (ELE SR 2014-15)	m	15.00	24.00	Rupees Twenty Four Only
49	Supplying PVC/GI flexible conduit pipe....mm dia fixing on surface over inverted wooden plugs or phill plugs or rawl plugs and clamped using heavy gauge saddles at an interval of 300mm using NF screws and either end of the pipe terminated completely. (ELE SR 2014-15 Page-03, Item-1.8)	Nos	15.00	23.00	Rupees Twenty Three Only
50	Extra for supplying 4mm thick white plastic plate and covering for junction boxes of size 110mm conduit using necessary machine screws. (ELE SR 2014-15 Page-11, Item26)	Nos	15.00	8.75	Rupees Eight And Paise Seventy Five Only
51	Supplying a 50mm wooden plug, tapered from 50x50mm to 25x25mm and fixing by using binding wire before concreting a roof slap. (ELE SR 2014-15 Page-15, Item27)	Nos	15.00	4.00	Rupees Four Only

Signature of the Contractor

EXECUTIVE ENGINEER-4
KRIDL BBMP DIVISION
BENGALURU-560 010

Executive Engineer,
Yelahanka Division,
BBMP, Bengaluru-64.